BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

No.BBMP/EE/DD/Ten/01/2015-16, Date:04.01.2016 **Indent No.20595**

SCHEDULE-B

NAME OF WORK: Construction of RCC drain in 2nd cross road at prashanath nagara in w no.13, Shetty halli sub division

Sl. No	Description of work	Unit	Qty	Rates Quoted by Contractor **R SHIVARAM**		
				In Figures (Rs.)	In Words (Rs.)	Cont AMOU
1	2	3	4	5	6	7
1	Earthwork excavation by manual means in ordinary soil invoiving in average horizontal throw up to 2m & an average lift upto 1.5m , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specfication & as per direction of Engineer-in-charge	Cum	295.65	79.0	Rupees Seventy Nine Only	23356.
2	Providing and laying in position plain cement concrete of nominal mix M 10 with OPC cement @ 220kgs, with 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specfication & as per direction of Engineer-in-charge	Cum	59.13	4831.0	Rupees Four Thousand Eight Hundred Thirty One Only	285657.
3	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with with 20mm and down size graded granite metal, coarse aggregate @ 0.69 cum and fine aggregates @ .460cum, with super plasticisers @ 3 liters confirming to is 9103-1999 reafairmed -2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings,pedastals,retaining walls, staircase, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specfication & as per direction of Engineer-in-charge	Cum	174.5	5718.0	Rupees Five Thousand Seven Hundred Eighteen Only	997791.(

Signature of the Contractor

Executive Engir

4	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	Qtl	104.7	6440.0	Rupees Six Thousand Four Hundred Forty Only	
5	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walss at any thickness,including attached pilasters,buttresses, plinth and string courses cost of all materials, labour complete as per specfication & as per direction of Engineer-in-charge	Sqm	866.9	283.0	Rupees Two Hundred Eighty Three Only	
6	Providing & laying reinforeced cement precast slabs of mix CC 1:11/2:3 using 20mm & down size graded Granite metal using HYSD 10mm dia steel @ 100mm c/c both ways & complete as per specfication & as per direction of Engineer-in-charge	Sqm	50.76	1504.0	Rupees One Thousand Five Hundred Four Only	
7	Disposal of debris to the final place of disposal with all lead and lift and as direction complete as per specfication & as per direction of Engineer-in-charge	Cum	295.65	78.0	Rupees Seventy Eight Only	2
					Total Percentage	2

Signature of the Contractor

Executive Eng
Dasarahalli Di

Signature of the Contractor

Executive